

## **Specifications**

55 Gallon Duplex Glycol Feed Unit D-55-100-2-PEFS

Furnish and install according to plans and manufacturers' instructions, a complete prefabricated, automatic glycol feed makeup unit. Each unit shall consist of a steel frame base, polyethylene tank with hinged removable cover, low water cut-off alarm, two brass rotary vane pumps with built in suction strainers, Nema 4X control panel, brass suction and discharge piping, pump isolation valves, discharge check valves, pressure switches, pressure gauges, pressure relief valves, and interconnecting piping. The duplex unit is set up for use with two separate heating or cooling loop systems unless the ALT (alternator) option is used.

TANK AND BASE ASSEMBLY: Tank shall be 55-gallon industrial grade polyethylene with graduated scale. Cover shall be hinged with a stainless-steel piano hinge. The base assembly shall be made of structural steel welded together and painted with a powder coat process for high durability.

**PUMPS:** Pumps shall be rotary vane close coupled type with brass housing and built in suction strainers. Pump motors are open drip proof type, 1/3 hp, 110v, 1ph with built in auto reset thermal overload. Pumps will be capable of 2 GPM @100 PSI.

CONTROL PANEL: Electrical control panel assembly shall be Nema 4X UL/CUL 508A listed, labeled and rated at 110v, 1ph, 60Hz. Panel shall have an audible alarm for low water, H.O.A. selector switches and yellow pilot lights for pump run, off-on selector switch and green pilot light for unit power, off-on selector switch and red pilot light for low water alarm, circuit breaker protection, motor rated starter relays, auxiliary contacts for alarm circuit and a 110v, 1ph, 9ft plug in power cord.


SUCTION AND DISCHARGE PIPING: Suction piping shall be brass with drain connection and plug. Suction isolation valve shall be a brass body gate. Discharge piping shall be brass with a brass body check valve, field adjustable pressure switch, pressure gauge, pressure relief valve and ½" N.P.T. male discharge pipe connection. Interconnecting piping to and from pump will be high pressure poly reinforced braided hose.


**LOW LEVEL SWITCH:** Float switch shall be made of ABS plastic. The float will be tethered on the upper portion of the tank. Low tank level will deactivate all pumping operations and activate a low level visual and audible alarm on the control panel.

## CTANDADD CVCTEM CETTINGS

STANDARD SYSTEM SETTINGS:		
G.P.M. <u>2.0</u> SYSTEM PRESSURE: ON – <u>10 PSI</u> / OFF – <u>40 PSI</u>		
PRESSURE RELIEF VALVE: 100 PSI		
POWER REQUIREMENTS:		
VOLTAGE:	: <u>110v / 1ph / 60Hz</u> F.L.A. <u>15.0 AMPS</u>	
OPTIONS:		
Special system pressure settings. (ONPSI / OFFPSI)		
AMT	Timed mixing loop keeps glycol mixed in tank and cycles pump	
ALT	Pump alternator rotates lead pump in duplex single loop systems	
ET	Expansion tank, 2-gallon steel	
SET	Expansion tank, 2-gallon stainless steel	
ET-PRV Pressure reducing valve with 2-gallon expansion tank (8 – 50 psi pressure setting)		
HFP	High flow pump (4.5 gpm @ 100 psi)	
HLA	High water alarm	

- 1 TANK POLYETHYLENE 55 GALLONS
- 2 COVER POLYETHYLENE HINGED
- 3 ELECTRICAL PANEL UL/CUL 508A
- 4 BASE ASSEMBLY
- 5 PUMP 1 ASSEMBLY
- 6 SUCTION ISOLATION VALVE PUMP 1
- 7 CHECK VALVE PUMP 1
- 8 PRESSURE GAUGE PUMP 1
- 9 PRESSURE SWITCH PUMP 1
- 10 PRESSURE RELIEF VALVE PUMP 1
- 11 FLOAT SWITCH (LOW WATER)
- 12 PUMP 2 ASSEMBLY
- 13 SUCTION ISOLATION VALVE PUMP 2
- 14 CHECK VALVE PUMP 2
- 15 PRESSURE GAUGE PUMP 2
- 16 PRESSURE SWITCH PUMP 2
- 17 PRESSURE RELIEF VALVE PUMP 2





Job Name	Contractor
Order No	Submitted ByDate
Sales Rep	Approved ByDate
Engineer	Notes
Location	

The specifications contained in this bulletin were effective at the time of publishing. We reserve the right to discontinue products at any time or to change specifications or design without incurring any obligation.

